JURUKUR BAHAN KONSULTANT (SABAH)
(BQSM Reg. No: 1993/FS00087 MOF Reg. No: 465-00000586)
Chartered Quantity Surveyors • Construction Cost Consultants
Project Managers • Construction Contract Consultants

3rd Floor, Lot 8, Block A,
Damai Plaza, Luyang,
P. O. Box 14125,
88847 Kota Kinabalu, Sabah.
Tel: (088)-219149, 239016
Fax: (088)-215800
Email: jbksabah@yahoo.com.sg
website: www.jbksabah.com

Ruj. Kami: POC/012020/KPKT/40

28hb Jun 2022

Alasim Omar Architect
F-27-1, Royal Plaza Putatan,
KM 11.2, Jalan Putatan,
88200, Kota Kinabalu, Sabah

(u/p: Ar. Datu Alasim Datu Omar)

Tuan,

PEMBINAAN BALAI BOMBA DAN KUARTERS PUTATAN, SABAH

~ Anggaran Kos Untuk Rainwater Downpipe

Perkara di atas adalah dirujuk.

2. Bersama-sama ini dikemukakan anggaran kos bagi kerja-kerja Rainwater Downpipe di bangunan Menara Latihan untuk tindakan pihak tuan selanjutnya.

3. Untuk makluman, harga yang digunakan adalah mengikut harga di dalam Kontrak.

Sekian, terima kasih.

Yang benar,
JURUKUR BAHAN KONSULTANT (SABAH)

b/p
ORSON M L LO
Principal
OL/MK/fm

cc.

KPKT(Unit Seni Bina)	(Attn : Ar. Nor Izyan Saleh)	Fax : 03-8891 3888
Perunding Ideal	(Attn : Ir. Gabriel Wong/Mr. JS Park)	Fax : 088-258796
Jurutera Perunding Intelek Sdn. Bhd.	(Attn : Ir. Hj Mohd Dzulkifli/Ir. Sherman Daim)	Fax : 088-384003
MTR Enterprise Sdn Bhd	(Attn: Mr. Sufian Sustreno)	

PEMBINAAN PROJEK BALAI BOMBA DAN KUARTERS PUTATAN, SABAH
KPKT/BPEMB/UB/T/20/2020

Anggaran Kos Bagi Kerja-kerja RWDP Di Bangunan Menara Latihan

ITEM	DESCRIPTION	UNIT	QTY	CONTRACT RATE (RM)	AMOUNT (RM)
	ROOF				
	Rainwater Disposal				
A	100mm diameter rainwater down pipe and fittings fixed vertically to wall or column with and including brackets at approved centres	m	18	46.00	828.00
B	Extra over for 90° bend	no	2	11.50	23.00
C	Ditto laid under ground floor slab including mass concrete (1:3:6) surround and shallow trench excavation etc.	m	6	46.00	276.00
D	Galvanised iron wire grating and setting on top of 75mm×75mm rainwater downpipe.	no	1	57.50	57.50
	ROOF				
	RWDP MENARA LATIHAN				**1,184.50**