JURUKUR BAHAN KONSULTANT (SABAH)
(BQSM Reg. No: 1993/FS00087 MOF Reg. No: 465-00000586)
Chartered Quantity Surveyors • Construction Cost Consultants
Project Managers • Construction Contract Consultants

3rd Floor, Lot 8, Block A,
Damai Plaza, Luyang,
P. O. Box 14125,
88847 Kota Kinabalu, Sabah.
Tel: (088)-219149, 239016
Fax: (088)-215800
Email: jbksabah@yahoo.com.sg
website: www.jbksabah.com

Ruj. Kami: POC/012020/KPKT/51

22hb Ogos 2022

Alasim Omar Architect
F-27-1, Royal Plaza Putatan,
KM 11.2, Jalan Putatan,
88200, Kota Kinabalu, Sabah

(u/p: Ar. Datu Alasim Datu Omar)

Tuan,

PEMBINAAN BALAI BOMBA DAN KUARTERS PUTATAN, SABAH

~Anggaran Kos Bagi Kerja-Kerja Wall Cladding

Perkara di atas adalah dirujuk.

2. Bersama-sama ini dikemukakan anggaran kos bagi kerja-kerja wall cladding untuk tindakan pihak tuan selanjutnya.

3. Untuk makluman, harga yang digunakan adalah mengikut harga di dalam Kontrak.

Sekian, terima kasih.

Yang benar,
JURUKUR BAHAN KONSULTANT (SABAH)

s/t

ORSON M L LO
Principal
OL/MK/fm

cc.

KPKT(Unit Seni Bina)	(Attn : Ar. Nor Izyan Saleh)	Fax : 03-8891 3888
Perunding Ideal	(Attn : Ir. Gabriel Wong)	Fax : 088-258796
Jurutera Perunding Intelek Sdn. Bhd.	(Attn : Ir. Hj Mohd Dzulkifli/Ir. Sherman Daim)	Fax : 088-384003
MTR Enterprise Sdn Bhd	(Attn: Mr. Sufian Sustreno)	

PEMBINAAN PROJEK BALAI BOMBA DAN KUARTERS PUTATAN, SABAH
KPKT/BPEMB/UB/T/20/2020

Bill No.2- Balai Bomba

ITEM	DESCRIPTION	UNIT	QTY	RATE (RM)	OMISION	ADDITION
	EXTERNAL WALLS					
	Omit					
	Groove Line					
A	EXTRA over for forming 30mm thick x 15mm recess groove line	m	(121.00)	5.00	(605.00)	
	Omit					
	Aluminium Cladding					
B	Supply and fix aluminium clading to manufacturer's detail. Refer drawing Architect's:200413/JBPMput/05	m2	(30.00)	920.00	(27,600.00)	
	Add					
	Aluminium Cladding					
C	Supply and fix aluminium clading to manufacturer's detail. Refer drawing Architect's:200413/JBPMput/T-31	m2	142	920.00		130,640.00
	WALL FINISHES					
	Prepare and apply one coat alkali resisting wall sealer and two finishing coats of approved acrylic weather resistant paint, externally to					
D	Plainface wall, column, beams and the like	m2	(112.00)	18.30	(2,049.60)	
	EXTERNAL WALLS				**(30,254.60)**	**130,640.00**
	COST ESTIMATE WALL CLADDING					**100,385.40**

Cost Estimate Cladding